

VALVE ELECTRONIC

CV446

GENERAL POST OFFICE: E-IN-C (W)

Specification: GPO/CV446/Issue 2. Dated: November, 1952 To be read in conjunction with K 1001	<u>SECURITY</u>	
	<u>Specification</u> Unclassified	<u>Valve</u> Unclassified

→ indicates a change

<u>TYPE OF VALVE:</u> Single Ended Water Cooled R/F Triode <u>CATHODE:</u> Directly Heated <u>ENVELOPE:</u> Copper/Glass <u>PROTOTYPE:</u> 3Q/260E			<u>MARKING</u> See K1001/4	
<u>RATING</u>		Note	<u>BASE</u> See Drawing, page 3.	
			<u>CONNECTIONS</u>	
			Pin	Electrode
Heater Voltage (V)		10.0	1	Filament
Heater Current (Nominal) (A)		80.0	2	Grid
Peak Usable Emission (A)		35.0	3	Filament
→ Max. Direct Anode Voltage (kV)	13.0		4	Grid
Max. Anode Dissipation (kW)		20.0	-	Anode Clamp
Max. Grid Dissipation (W)		800.0		
Max. R.F. Grid Current per lead (A)		30.0		
Amplification Factor		35.0	A	
Impedance		1400.0	A	
→ Max. Freq. for above Ratings	30 Mc/s			<u>DIMENSIONS</u> See Drawing, page 3
<u>CAPACITANCES (pF)</u>				<u>PACKAGING</u> See K1005
→ C _{ag}	29.0			
→ C _{gf}	42.0			
→ C _{af}	0.9			
<u>NOTE</u>				
A. Measured at V _a = 2 kV, I _a = 2 A.				

TESTS

To be performed in addition to those applicable in K1001

	Test Conditions				Test	Limits		No. Tested	Note
	Vf (V)	Vg1 (V)	Va (kV)	Ia (A)		Min.	Max.		
a	10.0	-	-	-	Filament Current (A)	75.0	85.0	100%	1,2.
b	10.0	Adjust record V1g1	6.0	1.0	-I _{g1} (μA)	-	100.0	100%	1,2.
c	10.0	Adjust record V2g1	4.0	1.0	Amplification Factor $\mu = \frac{2000}{V1g1 - V2g1}$	30.0	38.0	100%	1,2.
d	10.0 10.0	+50 +100	2.0 2.0	Record Ia1 Record Ia2	Mutual Conductance $gm = \frac{Ia2 - Ia1}{50 \text{ mA/V}}$	18.0	28.0	100%	1,2.
e	10.0	3000	3.0	-	Peak Emission I _e (A)	50	-	100%	3
f	10.0	Record V3g1	10.0	0.5	Cut-off Test V3g1 (V)	-200	-280	100%	

NOTES

- For this and all subsequent tests (except test 'e') the filament shall be heated by 50 c.p.s. current and the carrier return of both anode and grid circuits shall be made to the centre tap of the filament transformer secondary.
- For all tests the water flow to the anode shall be adjusted to 12½ gallons per minute at 45 lbs/in pressure.
- Test 'e' shall be carried out by measurement of the discharge of a condenser charged to 3 kV and connected between grid and anode strapped and one end of the filament.

